

NEW - Prefab Wood Office Kits — 20', 40' & Combos



NEW - Prefab Wood Office Kit

- CSIP-All required Container Structural Insulated Panels based on the kit ordered. The panels are made with 2"x3" wood studs 16" O.C. and have a 1/4" ACX plywood sheet as the finished face. All walls have an R-13 rating.
- Electrical Package-125 AMP Breaker Box, three 15-AMP and one 20 AMP breaker, two four foot fluorescent 2 bulb light fixtures, 12-2 Romex wire, exterior junction box, gang boxes pre-mounted in walls, one light switch, three outlets. All Products UL Rated.
- Weld-N-Go Systems™ —All offices come with two Weld-N-Go™ Windows and one Weld-N-Go™ Man Door. The 16 foot Office/Storage Combo Kits include a partition wall and a Weld-N-Go™ Field Goal Man Door.
- System does not require any special support systems to hold the walls or roof in place. All walls are toe nailed to the container floor and the roof is supported by the sidewall. Roof is suspended so electrical can run in any direction.
- A/C Unit —An 8,000 BTU Air conditioning unit with heat pump 115 Volt and A/C Cage is included in each office kit. Up grades to 12,000 BTU with heat pump or a Bard 1 Ton with heat pump is available.
- Accessories —Two gallons of gray floor paint, lockset, threshold plate, and door sweep are all included in the kit

Advantages

Quick Assembly—2 men at 2.75 HRS
Consistency of End Product
Durable
Ease of Install
Cost Effective

17232 S. Figueroa St., Gardena, CA 90248

